



MEMORANDUM

Missouri Department of Transportation Design District 10

TO: Kathy Harvey
State Design Engineer

Attention: Joe Jones

FROM: Andy Meyer
Transportation Project Manager

DATE: December 1, 2008

SUBJECT: 2009 Awards for Excellence in Practical Design
Submittal – J0S2163, Rte W, Scott County

Please find attached District 10's submittal of the above referenced project for consideration. The project addressed the need to replace a severely damaged bridge and re-open a rural route heavily utilized by agricultural traffic prior to the fall harvest.

Project History

The Southeast District experienced severe flooding in Spring 2008, resulting in significant damage to bridge structures across the district. Many of these structures were quickly repaired after the flooding through the cooperation of the headquarters and regional bridge maintenance groups.

Bridge P099 over Little River Drainage District Ditch 35 received a great deal of attention between March and April of 2008, including reinforced end bents and new back boards, but it became evident that attempts to stabilize the structure would not be successful. Previously spliced piling under the intermediate bents had failed at the splice due to lateral loading applied by an accumulation of drift during the flood, and the bridge would have to be closed to all traffic until it could be replaced.

Local officials, property owners, and farmers that depend on Route W for access to Oran and Route 77 strongly and effectively communicated their desire to see this bridge replaced as soon as reasonably possible. Farmers that utilized Route W were very specific in their communication that this road was essential to efficient planting and harvest. School administrators in Oran were also concerned about impacts to bus route when school began in the fall.

Project Schedule

In late April, in communication with the bridge division, we developed a schedule as follows to re-open the bridge prior to the fall harvest and start of school:

- PS&E submittal May 27, 2008
- Letting June 20, 2008
- Award July 2, 2008
- Early NTP July 16, 2008
- Open to traffic August 30, 2008.

Project Scope

In order to deliver the project within the very aggressive schedule described above, the project scope needed to be practical and realistic in terms of what we were trying to accomplish. We could not acquire right of way. We could not relocate utilities. We could not relocate access to adjacent properties. All the parameters listed above required that the bridge itself be reconstructed at the same profile grade and with a length approximating existing.

During the scoping fieldcheck, the core team committed to the following:

- Replace bridge with a single span box-beam structure, approximating the profile and length of existing. This was made possible by eliminating the intermediate bents, improving the hydraulic efficiency of the channel. Little River Drainage District signed off on the project specifically because of this design feature. Area farmers who were aware of the connection between drift and the damage/closure were very supportive of this design feature.
- Eliminate all approach guardrail and crashworthy end sections to allow existing field entrances to remain in place. This reduced grading to backfilling the bridge and dressing the approaches for paving.
- Set bridge width at 28 feet and bolt a standard tube rail system to the outside of the exterior beam. This maximized the usable opening for agricultural traffic and simplified the bridge to 7 – 4 ft. pre-cast box beam units. While eliminating one beam and going to a width of 24 feet would match the existing roadway, the efficiency in moving the rail out an additional 2 feet and eliminating all approach work was actually the most cost effective option. A low profile railing or differing beam widths were evaluated but discarded due to the increased design time necessary to implement.
- Road closure with traffic control maintained by MoDOT maintenance forces. Because the road was already closed, district maintenance simply maintained the existing traffic control until project completion.

Project Cost

	<u>Roadway</u>	<u>Bridge</u>	<u>Total</u>	
Preliminary Estimate*	160,000	200,000	360,000	
Project Award	63,065	170,358	233,423	
Total Savings	96,935	29,642	126,577	(35%)

* The preliminary estimate was based on a cost for a similar sized project that required a reasonable level of approach work and possible profile grade adjustment.

Conclusion

The bridge was completed and open to traffic on August 20, 2008, 9 days ahead of schedule. Keith Simpson of A.E. Simpson Construction commented that we had done everything short of eliminating the deck to simplify the structure and make construction quick and easy. This bridge has been used by the Southeast District as an example of what we are capable of accomplishing with the safe and sound program: a timely and practical solution to a rural bridge replacement.

2009 APPLICATION FORM

(required for each entry)

Complete this section for (check one):

Small Project

Large Project

Post-Design Solution

Off System Project

Job No. J0S2163 **Route** W **County / LPA** Scott Co & Little River Drainage Dist.

Description (attach separate sheet if necessary) Emergency contract to construct Bridge A7670 to replace Bridge P099 over Drainage Ditch 35 on Route W west of Oran. Bridge P099 was severely damaged during Spring 2008 flooding and was closed to all traffic until a replacement could be constructed. Roadway and bridge plans were completed in three weeks. The existing bridge was removed and the new bridge constructed in 6 weeks.

Project Leader Andy Meyer

Key Team Members (include key personnel irrespective of employer-nine individuals maximum)

Anousone Arounpradith SPM

Kieth Ferrel SHE

Brian Holt RE

Tom Farris SHD

Nathan Connor SCI

Joe Crader SGS

Stan Johnson AE

Jeff Wachter TPD

Mike Landers SDT

Project Budget:

Initial Cost / Estimate \$ 360,000 **Final Cost / Award** \$ 233,423

What would make this entry stand out from the rest of the entries when considering MoDOT's practical design philosophy? (In layman's terms - 200 words or fewer-attach separate sheet if necessary)

This is an example of carefully balancing the scope of the project with the desired timeline and resources available. This was an emergency replacement. We needed the bridge done and the road back open before the fall harvest. We needed to deliver an economical solution with the understanding that this project was not previously programmed and would need to be squeezed into the budget. We needed to produce plans and specifications within the few weeks available to make the award and construction possible prior to harvest. All these needs were met by taking a practical look at the site, matching existing hydraulic conditions, matching existing roadway geometrics, and simplifying the roadway and bridge design to the extent that beams could be quickly fabricated, the bridge quickly constructed, and the road re-opened. **When we discuss the goals of the Safe and Sound program with local officials, we use this bridge to illustrate the successful implementation of the program and the delivery of realistic practical solutions for rural bridge replacements.**

Send entries to: MoDOT Design Division, ATTN: Joe Jones
1320 Creek Trail Dr., Jefferson City, Missouri 65109

ALL ENTRIES MUST BE RECEIVED NO LATER THAN CLOSE OF BUSINESS ON DECEMBER 1, 2008



J0S2163 - Route W, Scott Co. – A7670 opened to traffic 8/18/2000





Project Summary

0S2163

Transportation Planning

2217 St. Marys Blvd.
P.O. Box 270
Jefferson City, MO 65102
Phone (573) 526-8058 Fax (573) 526-8052

Project Manager: ANDY MEYER
(Award Month): 7

Status: 4-ACCEPTED
(Award Year): 2008

Stage: SCOPING
SFY / (STIP SFY): 2009

Route Name	Begin Log	End Log	Begin County	TMA	Travelway ID
RT W E	1.75	1.85	Scott	N	305
RT W W	5.61	5.71	Scott	N	306

System	Func. Class	NHS	AADT	Confl.
Supplementary	Major Collector	N	53	N

Reason And Remarks	Emergency project to replace flood damaged bridge.
Detailed Description	Grading, paving and replace bridge P099 over Ditch 35
Location	1.8 miles east of Rte. P.

Funding Package 1:	Federal Oversight:	No	Primary Category:	1- EXISTING SYS (DIST)
Funding Package 2:	Fed. Funding Category:	B- BRIDGE	Secondary Category:	P- REHAB AND RECONST
Bonding SFY:	Capitalization Code:	1-C-CAPITALIZED	Work Type 1:	B- BRIDGE REPLACEMENT
Adv. Const/Payback:	Adv. RW Year:	0	Subwork Type:	
Work Miles:	Bridge Count:	1	Work Type 2:	
Parcel Count:	Track:	No	Work Type 3:	
Award Month:	Award Year:	0	Const. Award Cost:	0
Better Roads Brighter Future:	Tip Number:	No		

Cost Estimate Breakdown

Grading/Drain.	Base Surface	Bridge Est.	Misc.	Contract Est.	PE Spent	ACT RW Spent
40	60	200	60	360	0	0
				Constr. Conting.		ACT Utility Spent
				7	Const. Est.	0
				Utilities		
				0	Const. Cost	
				Non Contract	0	10,000.0%
				0	367	
				R/W Acquisition		
				0		0.0%
				R/W Incident.		
				0		
				Prelim. Engr.		
				40		
				Constr. Engr.		
				25		
				Ttl Incidental		
				65		
				Incent./Disincent.		
				0		
				Prog. Est. Ttl.		
				432		
					Prj. Ttl.	
					432	
						Lane Miles
						0.20
						Cost/Mile
						800.00

Project Costs

	Prior	2006	2007	2008	2009	2010	2011	2012	2013	Future	Prg Ttl	Total
Preliminary Engineering	0	0	0	0	40	0	0	0	0	0	40	40
Construction	0	0	0	0	367	0	0	0	0	0	367	367

Project ID: 10651
Let By: Central Office
Work District: 10
Length: 0.1
Est. Submittal Date: May 13, 2008

Planning Org	Federal District	Senate District	House District
BOOTHEEL REG PLAN & ECON DEV	8	27	160

MISSOURI DEPARTMENT OF TRANSPORTATION

DATE : 06/20/08
PAGE : X01 -1

VENDOR RANKING


CALL ORDER : X01
LETTING DATE : 06/20/08 11:00 a.m.
CONTRACT ID : 080620-X01
DISTRICT : 10
COUNTIES : SCOTT
CONTRACT DESCRIPTION : RURAL ROUTE
CONTRACT TIME : 08/31/08 COMPLETION DATE
PROJECT(S) : J0S2163

SET-ASIDE :


RANK	VENDOR NO./NAME	TOTAL BID	% OVER LOW BID
1	0010274 A. E. Simpson Construction Inc.	\$ 233,423.00	100.0000%
2	0010722 Robertson Contractors, Inc.	\$ 261,676.00	112.1038%
3	0010249 Penzel Construction Company Inc.	\$ 313,851.33	134.4560%

CERTIFIED BY
DESIGN
STATE DESIGN ENGINEER



P0099 Scott Rt W 03-25-08
drift @ span 3



P0099 Scott Rt W 03-25-08
sagging @ span 3




P0099 Scott Rt W 03-25-07
washout @ east approach



P0099 Scott Rt W 03-25-08
east abut washout

P0099 Scott Rt W 03-25-08
center span sagging @ span 3 north side



P0099 Scott Rt W 03-25-08
view to west

